



TIE DOWN SELECTION SCHEDULE

TIE DOWN	A	RANGE OF UNIT LENGTHS									
		6' WIDE	7' WIDE	8' WIDE	9' WIDE	10' WIDE	11' WIDE	12' WIDE	13' WIDE	14' WIDE	
L12	6"	8'-28'	8'-33'	8'-34'	8'-34'	8'-35'	8'-35'	8'-35'	8'-35'	8'-35'	8'-35'
L22	9"	29'-45'	34'-50'	35'-50'	35'-50'	36'-50'	36'-50'	36'-50'	36'-50'	36'-50'	36'-50'

NOTES:

1. L12 AND L22 TIEDOWNS WITH 1/4"x1-1/4" SHEET METAL SCREWS AND COVER AVAILABLE AS AN OPTION FROM ICS.
2. TIE DOWN ADEQUATELY RESISTS OVERTURNING, UPLIFT AND SLIDING LOADS DUE TO LOADS CONFORMING TO ASCE-7-88 AT 110 MPH, EXPOSURE C.
3. FOUR TIE DOWNS ARE REQUIRED PER BUILDING. INSTALL AT CORNERS OF EACH WALL.
4. WHEN ICS STORAGE UNIT IS ADJACENT TO ANOTHER BUILDING REDUCE OVERALL WIDTH OF FOUNDATION BY 6".
5. 8" MINIMUM CONCRETE DEPTH REQUIRED AT TIE DOWN.



INTERNATIONAL COLD STORAGE
 215 E. 13TH STREET, P.O. BOX 425
 ANDOVER, KS. 67002

800-835-0001
 FAX 316-733-2434

TIEDOWN DETAIL

DRAWING	DATE	SCALE	REVISED
AE190	2/10/00	NONE	

Visit us on the web at, www.icsco.com